1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Sound Transmission Loss RAL-TL18-347

<u>KAL-1L16-547</u>

Page 1 of 8

Sidney, OH
CONDUCTED: 2018-05-30

ON: 0.75# EVA with calcium carbonate filler

TEST METHOD

FOR: **Polyfill LLC**

Riverbank Acoustical LaboratoriesTM is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2005 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM E90-09 (2016): "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements." The single number rating of the specimen was calculated according to ASTM E413-16: "Classification for Rating Sound Insulation." A description of the measuring procedure and room qualifications is available upon request. The transmission loss values are for a single direction of measurement. The product designation used in this report was provided to RAL by the sponsor and attributed to the specimen under test.

DESCRIPTION OF THE SPECIMEN

The test specimen was designated by the manufacturer as 0.75# EVA with calcium carbonate filler. A full external visual inspection performed on the test specimen by Riverbank personnel verified the manufacturer's description.

Test Specimen

Material: Ethylene-vinyl acetate with calcium carbonate filler

Dimensions: 1219.2 mm (48 in.) x 2413 mm (95 in.)

Thickness: 2.16 mm (0.085 in.) Overall Weight: 10.89 kg (24 lbs)

Mass per Unit Area: Nominal @ 3.66 kg/m² (0.75 lb/ft²)

Measured @ 3.70 kg/m^2 (0.76 lb/ft²)



1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

An MALION Technical Center

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RIVERBANK.ALIONSCIENCE.COM

Test Report

RAL-TL18-347

Page 2 of 8

Polyfill LLC 2018-05-30

Physical Measures

Overall Dimensions: 1.22 m (48.00 in.) wide by 2.41 m (95.00 in.) high

Overall Thickness: 2.16 mm (0.09 in.) Overall Weight: 10.89 kg (24.00 lbs.) Transmission Area: 2.93 m² (31.50 ft²)

Mass per Unit Area: 3.71 kg/m² (0.76 lbs./ft²)

Test Aperture

Size: 1.22 m (4.0 ft.) by 2.44 m (8.0 ft.)

Filler Wall: None

Sealed: Entire periphery (both sides) with dense mastic

Test Environment

Source Room

Volume: 178.3 m³ (6297.6 ft³) Temperature: 23±0°C (73±1°F)

Humidity: 57±1%

Receive Room

Volume: $130.5 \text{ m}^3 (4607.0 \text{ ft}^3)$ Temperature: $23\pm0^{\circ}\text{C} (73\pm1^{\circ}\text{F})$

Humidity: 56±1%

Requirements

Temperature: 22° C +/- 2° C, not more than 3° C change over all tests. Humidity: $\geq 30\%$ RH, not more than +/- 3% change over all tests.



1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

RAL-TL18-347
Page 3 of 8

Polyfill LLC 2018-05-30



Figure 1 – Specimen mounted in test opening, as viewed from receive room



Figure 2 – Specimen as received, prior to installation



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

An MALION Technical Center

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

RAL-TL18-347
Page 4 of 8

Polyfill LLC 2018-05-30

TEST RESULTS

Sound transmission loss values are tabulated at the eighteen standard frequencies. A graphic presentation of the data and additional information appear on the following pages. The precision of the transmission loss test data is within the limits set by the ASTM Standard E90-09 (2016).

FREQ.	<u>T.L.</u>	<u>C.L.</u>	<u>DEF.</u>		FREQ.	<u>T.L.</u>	<u>C.L.</u>	<u>DEF.</u>
				-				
100	16	0.43			800	22	0.19	4
125	14	0.68			1000	24	0.17	3
160	13	0.36			1250	26	0.16	2
200	13	0.48	1		1600	28	0.12	
250	15	0.42	2		2000	29	0.11	
315	17	0.38	3		2500	31	0.07	
400	17	0.32	6		3150	32	0.07	
500	19	0.26	5		4000	34	0.08	
630	21	0.17	4		5000	36	0.10	

STC=24

ABBREVIATION INDEX

FREQ. = FREQUENCY, HERTZ, (cps)

T.L. = TRANSMISSION LOSS, dB

C.L. = SAMPLING PRECISION DURING TEST IN dB, FOR A 95% CONFIDENCE LIMIT

DEF. = DEFICIENCIES, dB<STC CONTOUR (SUM OF DEF = 30)

STC = SOUND TRANSMISSION CLASS

Dean Victor

Senior Experimentalist

Report by_

Malcolm Kelly

Acoustician

Approved by

Eric P. Wolfram

Laboratory Manager



Tested by

® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report


RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Page 5 of 8

Polyfill LLC 2018-05-30

SOUND TRANSMISSION REPORT

0.75# EVA with calcium carbonate filler



FREQUENCY (Hz)

STC=24 OITC=19

TRANSMISSION LOSS
SOUND TRANSMISSION LOSS CONTOUR



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Test Report

An MALION Technical Center

RAL-TL18-347
Page 6 of 8

Polyfill LLC 2018-05-30

APPENDIX A: Extended Frequency Range Data

Specimen: 0.75# EVA with calcium carbonate filler (See Full Report)

The following non-accredited data were obtained in accordance with ASTM E90-09 (2016), but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes. Sampling precision observed during this procedure is reported below.

1/3 Octave Band Center Frequency (Hz)	Sound Transmission Loss (dB)	Sampling Precision (95% ±)
31.5	8	0.75
40	12	0.85
50	11	0.57
63	5	0.73
80	7	0.75
100	16	0.43
125	14	0.68
160	13	0.36
200	13	0.48
250	15	0.42
315	17	0.38
400	17	0.32
500	19	0.26
630	21	0.17
800	22	0.19
1000	24	0.17
1250	26	0.16
1600	28	0.12
2000	29	0.11
2500	31	0.07
3150	32	0.07
4000	34	0.08
5000	36	0.10
6300	37	0.13
8000	38	0.12
10000	39	0.15
12500	40	0.23



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

RAL-TL18-347
Page 7 of 8

Polyfill LLC 2018-05-30

APPENDIX B: Determination of Outdoor Indoor Transmission Class (OITC)

Specimen: 0.75# EVA with calcium carbonate filler (See Full Report)

The determination of the Outdoor Indoor Transmission Class (OITC) as reported below was made with explicit conformity to the procedures described in the ASTM E1332-16 test standard. Test Method ASTM E90-09 (2016) was used to obtain the sound transmission loss data. This rating is based on an average transportation noise source spectrum and an A-weighted sound level reduction, either of which may be inappropriate for some applications.

One-third Octave Band	Reference Sound Spectrum,	Test Specimen		
Center Frequency, Hz	dB	Transmission Loss, dB		
80	103	7		
100	102	16		
125	101	14		
160	98	13		
200	97	13		
250	95	15		
315	94	17		
400	93	17		
500	93	19		
630	91	21		
800	90	22		
1000	89	24		
1250	89	26		
1600	88	28		
2000	88	29		
2500	87	31		
3150	85	32		
4000	84	34		

OITC = **19**



1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Polyfill LLC 2018-05-30

Page 8 of 8

APPENDIX C: Instruments of Traceability

Specimen: 0.75# EVA with calcium carbonate filler (See Full Report)

		Serial	Date of	Calibration
<u>Description</u>	Model	<u>Number</u>	Certification	<u>Due</u>
Bruel & Kjaer Pulse Analyzer - System4	Type 3560-C	2639093	2017-08-02	2018-08-02
Bruel & Kjaer Mic And Preamp D	Type 4943-B-001	2311440	2017-09-22	2018-09-22
Bruel & Kjaer Pistonphone	Type 4228	2781248	2017-08-02	2018-08-02
EXTECH_62	SD700	A.083662	2017-11-20	2018-11-20
EXTECH_63	SD700	A.083663	2017-11-20	2018-11-20

END



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.